Scope:- These specifications are intended to cover furnishing all labor, materials, etc. to completely waterproof the two roofs, with 4-ply built-up roofing, including flashing and counterflashing, drain boxes; also, all flashing and counterflashing around all mechanical trades, pipes, ventilators and other construction, projecting through the roofing, whether shown, specified or not.

General:- All materials to be Class "A".

The roofing to be applied by an approved roofing contractor.

Roof Deck:- The roofing contractor is to examine the surfacing of the roof slabs to see that they are as specified, and shown, including cants and crickets, and that they are properly pitched and graded as called for, and that all water, no matter where falling on the roofs, drains absolutely clear, i.e., that no water stands on the roofs, and that the roof surfacing has not been damaged by frost.

Roof Boxes:- Extreme care is to be taken in setting the roof boxes to insure the top of the gravel stops not projecting above the adjacent section of the roof.

Workmanship and Materials:- All workmanship and materials and all details to be first-class, in every respect, whether specified or shown.

Provision to be made in all copper and other metal